

Summit Lighting Upgrade RFI's Thru 5.1.26

1. Rooms 122,125,131,132 all have existing can lights. Can lights are not shown on the lighting cut sheets. The majority of the can lights are also in Drywall hard lids. Is the intent to upgrade the Can lights during this project?
 - a. Yes, Lighting should be updated with LED High Efficient lighting
2. Room 141 has an existing Edison Base screw in style Light bulb please advise if this fixture upgrade is part of the project. If so what style of fixture is desired?
 - a. Yes, Lighting should be updated with LED High Efficient lighting
3. Room 105 and stairwells 101,109 have shop lights hanging by all thread in them or surface mount. Is the intent to hang the 1x4 fixtures in the cut sheets in these areas?
 - a. Yes, Lighting should be updated with LED High Efficient lighting. Mounting Options to be decided by Contractor
4. Do you have a desired lumen or foot candle requirements for Classrooms, Hallways, Stairwells and Weld shop Area? Who would supply and install ceiling tiles if lighting requirements are met with fewer fixtures than the existing fixture quantities?
 - a. Lumens should follow industry standards of that typical to Classrooms, Office Space and egress pathways. Contractor is responsible for ceiling tiles if needed.
5. Alternates 2 and 3 call to integrate lighting controls, Dimmers ,Occupancy and Daylight sensors where required. Do you have a list of room requirement's for these items?
 - a. No, List of requirements, would have been seen during the Pre-Bid Site visit.
6. Is this work able to be preformed during 1st shift hours 7am to 4 pm?
 - a. Yes, work needs to be completed between 7am, and 4pm Monday through Friday.
7. All 3 of the stairwells have wall mounted fluorescent fixtures at each landing between floors. Is the intent to use the lay in style 1x4 fixtures in these locations with surface mount kits?
 - a. Wall mount may be used as long as the lighting sheds to the steps.